January 2006

NEW ACLAND COAL MINE STAGE 2 EXPANSION PROJECT

ENVIRONMENTAL IMPACT STATEMENT

Contents

Executive Summary

Glossary

1. Introduction 1-1

1.1 The Project 1-1
1.2 Project Description 1-1
1.3 Project Proponent 1-3
1.4 Study Team 1-4
1.5 Project Objectives and Scope 1-4
1.6 The Environmental Impact Assessment Process 1-4
1.6.1 Purpose of the EIS 1-4
1.6.2 Objectives of the EIS 1-5
1.6.3 Structure of the EIS 1-5
1.7 Public Consultation Process and Submissions 1-5
1.8 Project Approvals and Legislative Framework 1-6
1.8.1 Environmental Protection Act 1994 1-6
1.8.2 Mineral Resources Act 1989 1-10
1.8.3 Integrated Planning Act 1997 1-10
1.8.4 Water Act 2000 1-11
1.8.5 Aboriginal Cultural Heritage Act 2003 1-11
1.8.6 Queensland Heritage Act 1992 1-11
1.8.7 Nature Conservation Act 1992 1-12
1.8.8 Land Act 1994 1-12
1.8.9 Vegetation Management Act 1999 1-12
1.8.10 Transport Infrastructure Act 1994 1-12
1.8.11 Forestry Act 1959 1-12
1.8.12 Environment Protection and Biodiversity Conservation Act 1999 1-12
1.9 Project Need 1-13

2. Description of the Project 2-1

2.1 Key Elements of the Project 2-1
2.2 Project Need 2-1
2.3 The Coal Mine 2-4
2.3.1 Coal Resources and Coal Reserves 2-4
2.3.2 Resource Utilisation 2-5
2.3.3 Mining Tenures 2-5
2.3.4 Mining and Rehabilitation 2-5
2.3.5 Blasting 2-15
2.3.6 Mine Equipment 2-15
2.3.7 Mine Facilities and Infrastructure 2-15
2.4 Coal Handling and Processing 2-16
2.4.1 Coal Processing Chain 2-16
2.4.2 Product Coal 2-17
2.4.3 Dust Suppression 2-17
2.4.4 Coal Processing Waste Circuit 2-17
2.5 Coal Transport 2-19

2.6 Water Management 2-20
2.6.1 System Overview 2-20
2.6.2 Separation of Runoff 2-20
2.6.3 Coal Process and Industrial Area 2-20
2.6.4 Sediment Control 2-22
2.6.5 Mine Water Management 2-22
2.6.6 Water Supply 2-22
2.7 Coal Transport 2-23
2.7.1 Train Movements 2-23
2.8 Road Realignment / Closure 2-23
2.9 Construction 2-23
2.9.1 Schedule 2-23
2.9.2 Material Volumes and Equipment 2-23
2.9.3 Transport of Plant and Equipment 2-24
2.10 Fire Protection System 2-24
2.11 Workforce 2-24
2.11.1 Construction Phase 2-24
2.11.2 Operational Phase 2-24
2.12 Decommissioning 2-25
2.13 Project Alternatives 2-25
2.13.1 No Project 2-25
2.13.2 Alternative Locations 2-25
2.13.3 Mining Options 2-25
2.13.4 Mining Techniques 2-25
2.13.5 Coal Wash Plant 2-26
2.13.6 Location of Dams 2-26

3. Land Resources 3-1

3.1 Existing Environment 3-1
3.1.1 Existing Land Use and Tenure 3-1
3.1.2 Land Use and Planning Provisions 3-1
3.1.3 Native Title 3-6
3.1.4 Sensitive Environmental Areas 3-6
3.1.5 Topography 3-7
3.1.6 Climate 3-7
3.1.7 Geology 3-9
3.1.8 Soils 3-12
3.2 Land Suitability 3-21
3.2.1 Limitations for Rainfed Cropping 3-21
3.2.2 Limitations for Beef Cattle Grazing 3-25
3.2.3 Pre-Mine Land Suitability 3-28
3.2.4 Post Mine Land Use Suitability 3-28
3.3 Good Quality Agricultural Land 3-30
3.4 Erosion Potential and Control 3-30
3.5 Contaminated Land 3-34
3.5.1 Potential for Contamination 3-34
3.5.2 Sampling, Analysis & Results 3-35
3.5.3 Contamination Prevention and Control 3-37
3.6 Overburden Characterisation and Management 3-37

3.6.1 Geochemistry and Acid Rock Drainage (ARD) Characterisation of Mine Waste 3-37
3.6.2 Management of Waste Rock 3-41
3.7 Rehabilitation 3-41
3.7.1 Proposed Post Mining Land Use 3-41
3.7.2 Post-Mine Landform 3-41
3.7.3 Mine Rehabilitation Strategies 3-42
3.7.4 Progressive Rehabilitation 3-44
3.7.5 Topsoil Management 3-44
3.7.6 Revegetation 3-45
3.7.7 Rehabilitation Success Criteria 3-45
3.7.8 Rehabilitation Maintenance 3-45
3.7.9 Rehabilitation Monitoring 3-46
3.7.10 Decommissioning 3-46

4. Water Resources 4-1

4.1 Surface Water Resources – Existing Environment 4-1
4.1.1 Existing Regional Hydrology 4-1
4.1.2 Existing Local Hydrology 4-3
4.2 Surface Water Resources - Impacts 4-3
4.2.1 Impacts on Regional Hydrology 4-3
4.2.2 Mine Water Management 4-4
4.2.3 Lagoon Creek Flooding Assessment 4-8
4.3 Surface Water Resources - Mitigation Measures 4-13
4.3.1 Monitoring programs 4-13
4.4 Surface Water Quality 4-15
4.4.1 Aquatic Impacts 4-17
4.4.2 Increase of Sediment Input into Rivers and Streams 4-17
4.4.3 Ecological Impacts due to Increased Hydrological Disturbance 4-18
4.4.4 Water Quality 4-18
4.5 Groundwater Quality 4-19
4.5.1 Groundwater Hydrology 4-19
4.5.2 Groundwater Quality 4-36
4.6 Ground Water Resources – Potential Impacts 4-40
4.6.1 Impacts on Groundwater – During Mine Dewatering and Operation 4-40
4.6.2 Impacts on Groundwater – Post-Mining 4-47
4.7 Final Void Water Quality Assessment 4-48
4.7.1 Groundwater Resources 4-48

5. Nature Conservation 5-1

5.1 Terrestrial Flora and Fauna – Overview 5-1
5.1.1 Environment Protection and Biodiversity Conservation Act 1999 Matters 5-1
5.1.2 Field Survey Methods 5-2
5.2 Terrestrial Flora and Fauna – Existing Environment 5-5
5.2.1 Terrestrial Flora 5-5
5.2.2 Community Descriptions 5-6
5.2.3 Vegetation Corridors 5-8
5.2.4 Weeds of Management Concern 5-8
5.2.5 Terrestrial Fauna 5-8
5.3 Terrestrial Flora and Fauna - Impacts 5-13

5.4 Terrestrial Flora and Fauna - Mitigation Measures 5-13
5.4.1 Weed Management Strategies 5-14
5.4.2 Pest and Domestic Animal Management 5-14
5.4.3 Revegetation and Rehabilitation 5-14
5.4.4 Ongoing Monitoring of Flora and Fauna 5-15
5.5 Conclusions and Recommendations – Terrestrial Flora and Fauna 5-15
5.6 Aquatic Ecology 5-15
5.6.1 Background 5-15
5.6.2 Aquatic Habitat 5-17
5.6.3 Fish Communities 5-17
5.6.4 Aquatic Macroinvertebrates 5-18

6. Air Quality 6-1

6.1 Existing Environment 6-1
6.1.1 Climate 6-1
6.1.2 Existing Air Quality 6-5
6.2 Air Quality Legislation and Dust Criteria 6-7
6.2.1 Dust Concentration 6-7
6.2.2 Dust Deposition 6-8
6.3 Air Quality Impact Assessment 6-8
6.3.1 Sources of Air Emissions 6-8
6.3.2 Estimation of Dust Emissions 6-8
6.3.3 Modelling Methodology 6-11
6.3.4 Input Meteorology 6-12
6.4 Air – Potential Impacts 6-13
6.4.1 Current Operations 6-13
6.4.2 2015 Operations 6-16
6.4.3 Discussion 6-19
6.5 Other Issues 6-19
6.5.1 Odour 6-19
6.5.2 Jondaryan Rail Siding 6-19
6.5.3 Vegetation Impacts 6-20
6.5.4 Livestock and Wildlife Impacts 6-20
6.6 Greenhouse Gases 6-20
6.7 Air Quality Management Strategies 6-21
6.8 Monitoring 6-22
6.9 Conclusion 6-22

7. Noise and Vibration 7-1

7.1 Overview 7-1
7.2 Existing environment 7-1
7.2.1 Background noise levels 7-1
7.2.2 Local and regional meteorology 7-5
7.3 Noise - Legislative context 7-7
7.3.1 Environmental Protection (Noise) Policy 1997 7-8
7.3.2 Environmental Authority (EA) 7-8
7.3.3 Road traffic noise criteria 7-8
7.3.4 Project specific assessment criteria 7-9
7.4 Management of impacts on environmental values 7-9

7.4.1 Overview 7-9
7.4.2 Equipment noise levels 7-9
7.4.3 Noise level prediction methodology 7-10
7.4.4 Modelling results 7-11
7.4.5 Airblast overpressure and vibration 7-15
7.4.6 Road noise 7-16
7.4.7 Impacts on animals 7-17
7.5 Mitigation measures 7-17
7.5.1 Noise impacts 7-17
7.5.2 Airblast overpressure and vibration 7-18
7.6 Conclusions 7-18

8. Cultural Heritage 8-1

8.1 Existing Values 8-1
8.1.1 Previous Studies 8-1
8.1.2 Legislative Context 8-1
8.2 Assessment Methodology 8-2
8.2.1 Scientific Significance 8-2
8.2.2 Aboriginal Significance 8-3
8.3 Indigenous Cultural Heritage – Aboriginal Significance 8-3
8.4 Non-indigenous Cultural Heritage 8-4
8.5 Potential Impacts and Mitigation Measures 8-4
8.5.1 Indigenous Cultural Heritage 8-4
8.5.2 Non-Indigenous Cultural Heritage 8-5

9. Scenic Values 9-1

9.1 Introduction 9-1
9.2 Existing Visual Characteristics 9-1
9.2.1 Regional Landscape Characteristics 9-1
9.2.2 Local Landscape Characteristics 9-1
9.3 Methodology 9-1
9.3.1 Classification of Landscape Visual Quality 9-2
9.4 Potential Impacts and Mitigation Measures 9-2
9.4.1 Night Lighting 9-2
9.4.2 Sensitive Visual Receptors 9-2
9.4.3 Visually Prominent Elements of the Project 9-4
9.5 Proposed Mitigation Measures 9-10

10. Waste Management 10-1

10.1 Waste Management Regulations 10-1
10.1.1 Waste Definition 10-1
10.1.2 Waste Reporting 10-1
10.2 Waste Management Strategy 10-2
10.2.1 Waste Management Procedure 10-2
10.2.2 Cleaner Production 10-3
10.2.3 Waste Tracking 10-3
10.2.4 Spill Containment and Remediation 10-3
10.2.5 Waste Monitoring 10-3
10.3 Waste Inventory, Characteristics and Management 10-4
10.3.1 Waste Characteristics 10-4

10.3.2 Construction Wastes 10-4
10.3.3 Operational Wastes 10-5
10.3.4 Management of General Wastes 10-6

11. Infrastructure and Traffic 11-1

11.1 Existing Infrastructure and Facilities 11-1
11.1.1 Roads 11-1
11.1.2 Rail 11-1
11.1.3 Port Facilities 11-1
11.1.4 Telecommunications 11-3
11.1.5 Power 11-3
11.1.6 Water Supply 11-3
11.1.7 Stormwater 11-3
11.1.8 Sewerage 11-3
11.2 Existing Traffic 11-3
11.2.1 Existing Traffic Volumes 11-3
11.3 Impact of Road Realignments 11-3
11.3.1 Road Safety 11-3
11.3.2 Stock Routes 11-4
11.3.3 Traffic Management During Construction 11-4
11.3.4 Travel Times 11-4
11.3.5 Consultation with Stakeholders 11-5
11.4 Impacts of Construction Traffic 11-5
11.4.1 Construction Traffic Generation 11-5
11.4.2 Impacts on Road Pavement during Construction 11-6
11.5 Impacts of Operational Traffic 11-7
11.5.1 Operational Traffic Generation 11-7
11.5.2 Impacts on Road Pavement during Operation 11-9
11.6 Impacts on Infrastructure 11-9
11.6.1 Rail 11-9
11.6.2 Port Facilities 11-10
11.6.3 Telecommunications 11-10
11.6.4 Power Supply 11-10
11.6.5 Water Supply 11-10
11.6.6 Stormwater 11-10
11.6.7 Sewerage 11-10

12. Community Consultation 12-1

12.1 Communication Objectives 12-1
12.2 Consultation Strategies 12-1
12.2.1 Individual Meetings 12-2
12.2.2 Advertisements 12-2
12.2.3 Community Enquiries 12-2
12.2.4 Public Display and Community Information Session 12-3
12.2.5 Advisory Body Meetings 12-3
12.3 Results 12-4
12.4 Consultation Summary 12-5

13. Social Environment 13-1

13.1 Existing Environment 13-1

13.2 Methodology 13-1
13.2.1 Community Consultation 13-1
13.3 Socio-Demographic Profile 13-2
13.3.1 Population Structure and Growth 13-2
13.3.2 Age and Gender 13-2
13.3.3 Employment and Labour Force Participation 13-3
13.3.4 Housing and Accommodation 13-4
13.4 Community Infrastructure and Services 13-5
13.4.1 Statutory Services 13-6
13.4.2 Health and Community Services 13-6
13.4.3 Education Facilities 13-6
13.4.4 Recreational, Cultural and Sporting Facilities 13-7
13.4.5 Service Clubs 13-7
13.4.6 Tourist Attractions 13-7
13.4.7 Public and Shopping Facilities 13-7
13.4.8 Tourist Accommodation 13-7
13.5 Local Community Values and Lifestyles 13-8
13.5.1 On-farm Activities near the Proposed Project 13-8
13.5.2 Properties Directly Affected by the Project 13-8
13.6 Potential Impacts and Mitigation 13-8
13.6.1 Lifestyle, Amenity and Community Cohesion 13-8
13.6.2 Demographic Profile 13-8
13.6.3 Impacts on the Social Profile 13-9
13.6.4 Ability to Live in Accordance with Values and Priorities 13-9
13.6.5 Housing Demand and Supply 13-9
13.6.6 Property Values and Marketability 13-9
13.6.7 Local Enterprises 13-10
13.6.8 Community Facilities, Services and Access 13-10
13.6.9 Cultural Profile 13-10
13.6.10 Summary 13-10

14. Economic Impacts 14-1

14.1 History of large scale development in the region 14-1
14.2 Existing Economic Environment 14-1
14.2.1 Location and Economic context 14-1
14.2.2 Employment and business 14-2
14.2.3 Future opportunities 14-4
14.3 Economic Impacts 14-4
14.3.1 Economic Modelling 14-5
14.3.2 Previous Work on Input-Output Studies 14-5
14.3.3 Input-Output Methodology 14-6
14.3.4 Construction Phase Impacts 14-6
14.3.5 Operational Phase Impacts 14-7
14.3.6 Impacts on Regional Workforce 14-8

15. Hazard and Risk 15-1

15.1 Overview 15-1
15.1.1 Legislative Compliance 15-1
15.1.2 Project Health and Safety Standards 15-1

15.1.3 Inventory of Dangerous Goods 15-1
15.2 Project Risk Assessment 15-3
15.2.1 Method 15-3
15.2.2 Risk Analysis Criteria 15-4
15.2.3 Hazard Identification and Assessment 15-6
15.2.4 Risk Assessment - Conclusion 15-10
15.3 Construction and Operations Impacts and Controls 15-10
15.3.1 Emergency Response 15-10
15.3.2 Risk Control Measures 15-10
15.3.3 Construction and Operation Safety Issues 15-12
15.3.4 Security 15-15
15.3.5 Explosives 15-15
15.3.6 Health and Safety Management Systems 15-16
15.3.7 Future Risk Assessment 15-16
15.3.8 Monitoring 15-17
15.3.9 Emergency Planning 15-17

16 Draft Environmental Management Plan 16-4

16.1 Introduction 16-4
16.1.1 The Project 16-4
16.1.2 Location 16-4
16.1.3 Project Description 16-4
16.1.4 Project Proponent 16-6
16.1.5 Structure of the EM Plan 16-6
16.1.6 Purpose of the EM Plan 16-6
16.1.7 Mining Leases 16-6
16.1.8 Project Name 16-6
16.1.9 Real Property Descriptions 16-6
16.1.10 Description of Land within the Mining Tenements 16-8
16.1.11 Neighbouring Land 16-8
16.2 Project Description 16-8
16.2.1 Description of the Mine 16-8
16.2.2 Mining Process 16-8
16.2.3 Mine Rehabilitation 16-9
16.2.4 Description of Coal Processing and Handling 16-9
16.2.5 Water Management 16-10
16.2.6 Sewage Treatment 16-10
16.2.7 Mining Related Activities 16-10
16.2.8 Environmental Management System 16-11
16.3 Environmental Values, Potential Impacts, Commitments, Proposed Draft Conditions And Supporting Information 16-11
16.3.1 Content of the Section 16-11
16.3.2 General 16-12
16.3.3 Air Quality 16-14
16.3.4 Water Resources 16-18
16.3.5 Noise and Vibration 16-29
16.3.6 Land Management 16-33
16.3.7 Nature Conservation 16-43
16.3.8 Waste Management 16-47

16.3.9 Community 16-51
16.3.10 Cultural Heritage 16-52
16.4 Monitoring 16-53
16.4.1 Background 16-53
16.4.2 Proposed Environmental Protection Objective 16-53
16.4.3 Commitments 16-53
16.4.4 Proposed Environmental Authority Conditions : Schedule J – Monitoring and Reporting 16-53
16.5 Reporting 16-54
16.5.1 Objective 16-54
16.5.2 Commitments 16-54
16.6 Continuous Improvement 16-54
16.6.1 Environmental Management System 16-54
16.6.2 Studies and Investigations 16-54
16.6.3 Research 16-54
16.7 Staff Training 16-54
16.8 Environmental Auditing and Review 16-55
16.8.1 Background 16-55
16.8.2 Objective 16-55
16.8.3 Commitments 16-55
16.9 Definitions 16-56
16.10 References 16-59

Appendix A Monitoring Maps 16-61

17. References 17-1

Appendix A Study Team

Appendix B Final Terms of Reference

Appendix C Standard Criteria

Appendix D Technical Data

List of Tables

Table 1-1 Key Approvals required for the Project 1-6

Table 2-1 Project Product Coal Reserves – Stage 2 Expansion (North, South and Centre Pits) 2-4

Table 2-2 Indicative Mine Equipment – New Acland Coal Mine Stage 2 Expansion 2-15

Table 2-3 Coal Handling and Preparation Plant – Throughput and Mass Balance 2-17

Table 2-4 Project Road and Rail Tonnage Increases – Mine Expansion 2-19

Table 2-5 Indicative Construction Schedule 2-23

Table 2-6 Construction Phase Material Quantities 2-23

Table 2-7 New Acland Coal Mine – Approximate workforce requirements over time 2-24

Table 3-1 State Planning Policies 3-3

Table 3-2 Outcomes 1 – 3 SPP 1/03 3-4

Table 3-3 Development Outcomes Under SPP 1/02 3-5

Table 3-4 Climate Averages, Oakey Aerodrome (BoM, 2005) 3-7

Table 3-5 Land Suitability Classes for Dryland Cropping – Pre-Mining (MLA 50216) 3-28

Table 3-6 Land Suitability Classes for Pasture – Pre-Mining 3-28

Table 3-7 Pre and Post Mine Land Suitability – Rainfed Cropping for Stage 2 Expansion 3-29

Table 3-8 Pre and Post Mine Land Suitability – Cattle Grazing for Stage 2 Expansion 3-29

Table 3-9 Erosion Causes and Control – Mining Activities 3-34

Table 3-10 Contaminated Land Assessment – 1999 Analytical Results 3-35

Table 3-11 Summary of acid forming characteristic test results for waste rock material 3-38

Table 3-12 Distribution of geochemical types 3-39

Table 3-13 Indicative Rehabilitation Schedule – MLA 50216 3-44

Table 4-1 Rainfall and Evaporation Gauge details 4-2

Table 4-2 Lagoon Creek – Catchment Parameters 4-3

Table 4-3 Lagoon Creek – Calculated Peak Discharge 4-3

Table 4-4 Sediment Basin Design Parameters 4-4

Table 4-5 Sediment Basin Design 4-5

Table 4-6 Mine Water Balance Catchment Areas 4-6

Table 4-7 Catchment Runoff Coefficients 4-7

Table 4-8 Mine Water Inflows and Demands 4-7

Table 4-9 Proposed Evaporation Dam Sizing 4-8

Table 4-10 Lagoon Creek HecRAS Modelling Results 4-9

Table 4-11 Lagoon Creek HecRAS Modelling Results continued 4-12

Table 4-12 Receiving water discharge criteria, New Acland Coal Mine. 4-13

Table 4-13 Summary data for Suspended Solids (mg/L) monitored at NAC 4-16

Table 4-14 Summary data for pH monitored at NAC 4-16

Table 4-15 Summary data for conductivity (uS/cm) monitored at NAC 4-17

Table 4-16 Summary of Groundwater Related Studies, New Acland Coal Mine and Surrounds 4-21

Table 4-17 Pumping Test Summary – Helidon Sandstone 4-25

Table 4-18 Number of Bores Installed Within Each Aquifer 4-28

Table 4-19 Groundwater Allocations 4-31

Table 4-20 Locations of existing and approved Helidon Aquifer pumping bores 4-35

Table 4-21 pH and Electrical Conductivity of Aquifers 4-37

Table 4-22 Summary of Groundwater Quality Compared to Drinking Water, Irrigation and Stockwater Guidelines – Basalt groundwater 4-37

Table 4-23 Summary of Groundwater Quality Compared to Drinking Water, Irrigation and Stockwater Guidelines – Coal Measures groundwater 4-38

Table 4-24 Summary of Groundwater Quality Compared to Drinking Water, Irrigation and Stockwater Guidelines – Hutton Sandstone groundwater 4-39

Table 4-25 Summary of Groundwater Quality Compared to Drinking Water, Irrigation and Stockwater Guidelines – Helidon Sandstone groundwater 4-39

Table 4-26 Predicted groundwater dewatering rates (ML/yr) for New Acland Coal Mine, 2006-2028 (excluding rainfall input) 4-40

Table 4-27 Groundwater levels (m AHD), with Dalby ARO pumping 4-44

Table 4-28 Groundwater levels (m AHD), without Dalby ARO pumping 4-45

Table 5-1 Vegetation communities of Project area 5-5

Table 5-2 Declared Pest Plants Identified at the Project site 5-8

Table 5-3 Pest Plants of Management Concern Identified at the Project site 5-8

Table 5-4 Area of regional ecosystems to be cleared 5-13

Table 6-1 Summary of climate data, Oakey, Bureau of Meteorology data 6-2

Table 6-2 Summary of PM_{10} monitoring near New Acland mine 2003-2004 6-6

Table 6-3 Summary of dust deposition monitoring near New Acland mine 2003-2004 6-6

Table 6-4 Summary of assumed New Acland pre-mining background dust levels 6-7

Table 6-5 EPP (Air) goals for ambient air concentrations of selected pollutants 6-7

Table 6-6 Current and 2015 Operational Information and Mining Required Information 6-9

Table 6-7 Summary of parameters required for emission estimations 6-9

Table 6-8 Summary of Emission Factors and Dust Control 6-10

Table 6-9 Estimated dust emissions (g/s) for current and 2015 operations 6-11

Table 6-10 Predicted dust concentrations and deposition rates at nearby sensitive receptors (including background levels) – current operations 6-13

Table 6-11 Predicted dust concentrations and deposition rates at nearby sensitive receptors (including background levels) for 2015 6-16

Table 6-12 Summary of relevant Greenhouse Gas emission factors 6-20

Table 6-13 Summary of Greenhouse Gas Emissions 6-21

Table 7-1 Summary of previous background monitoring results (Huson & Associates, 1996) 7-1

Table 7-2 Summary of previous background monitoring results (Ison Environmental Planners, 1999). 7-3

Table 7-3 Average monthly LA90,15min noise levels for the night period at a variety of locations around the existing mine site (Moore and Associates, 2002 – 2005) 7-3

Table 7-4 Summary of long term noise monitoring results for Location 1 from 30/3/05 – 7/4/05 7-4

Table 7-5 Summary of long term noise monitoring results for Location 2 from 30/3/05 – 7/4/05 7-4

Table 7-6 Summary of long term noise monitoring results for Location 3 from 30/3/05 – 7/4/05 7-5

Table 7-7 Current Noise legislation and guidelines 7-7

Table 7-8 Noise limits for sensitive places (EPA, 2004b) 7-8

Table 7-9 Airblast overpressure and vibration limits in sensitive places (EPA, 2004b) 7-8

Table 7-10 Road traffic noise criteria (State of Queensland, 2004) 7-8

Table 7-11 Typical mining equipment sound power data 7-10

Table 7-12 Modelling results for 2007 operational scenario 7-11

Table 7-13 Modelling results for 2011 operational scenario 7-11

Table 7-14 Modelling results for 2015 operational scenario 7-12

Table 7-15 Blasting parameters 7-15

Table 7-16 Overburden blasting – vibration values at various distance from the blast 7-16

Table 9-1 Scenic Values – Mitigation Measures 9-11

Table 10-1 Waste Management: Construction Phase 10-4

Table 10-2 Mining Wastes 10-5

Table 10-3 Waste Management: Operation Phase 10-6

Table 11-1 Traffic Volumes – Regional Roads 11-4

Table 11-2 Estimated Vehicle Trips Generated During Project Construction 11-6

Table 11-3 Schedule of Coal Transport 11-8

Table 11-4 Estimated Vehicle Trips generated per day during Mine Operation 11-8

Table 11-5 Coal Transport by Rail – Breakdown 11-9

Table 12-1 Environmental and social concerns identified through stakeholder consultation 12-4

Table 13-1 Rosalie Shire Population Age and Gender 2001 13-3

Table 14-1 Employment by industry in Rosalie and Darling Downs SD 14-3

Table 14-2 Employment trends from 1996 to 2001 for Rosalie Shire 14-4

Table 14-3 Type 2 economic multipliers for the Darling Downs Region – $ per million 14-6

Table 14-4 Construction impacts on Darling Downs region and the State 14-7

Table 14-5 Annual Operational Impacts of the Project on the regional economy (Darling Downs SD) 14-8

Table 14-6 Labour Market Implications of Expanded Labour Demand – Darling Downs SD 14-9

Table 14-7 Occupational Distribution Darling Downs Region and Rosalie Shire – 2001 14-10

Table 15-1 Legislative Compliance 15-1

Table 15-2 Indicative List of Dangerous Goods and Hazardous Substances 15-2

Table 15-3 Indicative List of Dangerous Goods and Hazardous Substances – Construction 15-2

Table 15-4 Indicative List of Dangerous Goods and Hazardous Substances - Operations Phase 15-2

Table 15-5 Likelihood of Occurrence for Hazardous Incidents 15-5

Table 15-6 Consequence Classes for Health and Safety and Environmental Losses 15-5

Table 15-7 Risk Assessment Matrix 15-5

Table 15-8 Risk Assessment Table – Construction Phase 15-6

Table 15-9 Risk Assessment Table – Operations Phase 15-7

Table 15-10 New Acland Tailings Storage Facility – ANCOLD Consequence Assessment 15-9

Table 15-11 Emergency Plan Elements for Mine-Site Related Emergencies 15-18

List of Figures

Figure 1-1 New Acland Coal Mine General Location Plan 1-2

Figure 2-1 New Acland Project Layout 2-2

Figure 2-2 New Acland Coal Mining, Preparation and Transport Process 2-3

Figure 2-3 Acland – Sabine Sequence Stratigraphy 2-6

Figure 2-4 New Acland Mine Sequence 2-8

Figure 2-5 Working Cross Section Through Pit 2-9

Figure 2-6 New Acland Mine 2007 2-10

Figure 2-7 New Acland Mine 2015 2-11

Figure 2-8 New Acland Mine 2020 2-12

Figure 2-9 New Acland Coal Mine – End of Mine 2-13

Figure 2-10 Coal Handling and Preparation Plant Process Flowsheet 2-18

Figure 2-11 New Acland Water Management System Schematic 2-21

Figure 3-1 New Acland Land Tenure 3-2

Figure 3-2 New Acland Topography 3-8

Figure 3-3 New Acland Geology 3-11

Figure 3-4 New Acland – Soil Sampling Sites and Soil Mapping Units 3-13

Figure 3-5 Pre-Mine Land Suitability Map for Rainfed Cropping - Stage 2 Expansion 3-23

Figure 3-6 Pre-Mine Land Suitability Map for Improved Pasture - Stage 2 Expansion 3-26

Figure 3-7 Post-Mine Land Suitability Map for Rainfed Cropping – Stage 2 Expansion 3-31

Figure 3-8 Post-Mine Land Suitability Map for Improved Pasture - Stage 2 Expansion 3-32

Figure 3-9 Rosalie Shire - Good Quality Agricultural Land 3-33

Figure 3-10 Contaminated Land Investigation Sites 3-36

Figure 4-1 Regional Watercourses 4-1

Figure 4-2 Mine Outline and Major Waterways 4-2

Figure 4-3 Average Monthly Rainfall Data (041024) and Evaporation Data (041359) 4-2

Figure 4-4 Lagoon Creek Surveyed Cross Section Locations 4-10

Figure 4-5 Developed Case (with Levee) 4-11

Figure 4-6 Water Monitoring Locations 4-14

Figure 4-7 Location of NAC Extraction Bores. Locations are in AMG 84 coordinates. 4-20

Figure 4-8 Schematic diagram of aquifers beneath the Project 4-22

Figure 4-9 Bouguer Gravity survey of Cecil Plains Sub-Basin. Blue colours infer basement lows; red colours infer basement highs. White polygons indicate the boundaries of existing and proposed NAC project areas. Locations are in AMG 84 coordinates. (Image courtesy of Peter Ellis, New Hope Coal Australia) 4-26

Figure 4-10 Bouguer Gravity survey of Cecil Plains Sub-Basin with grid mesh (white lines) of Helidon Sandstone Aquifer numerical model superimposed. Black lines show inferred structural features. White polygons indicate the boundaries of existing and proposed NAC project areas. 4-27

Figure 4-11 Location of NAC Monitoring Bores. Locations are in AMG 84 coordinates 4-29

Figure 4-12 Location of Private Groundwater Facilities 4-30

Figure 4-13 Representative Coal Measures Water Level Fluctuation Within Monitoring Bores Surrounding the Project Since 2002 4-33

Figure 4-14 Representative Basalt Water Level Fluctuation Within Monitoring Bores Surrounding the Project Since 2002 4-33

Figure 4-15 Regional Potentiometric Surface – Walloon Coal Measures. Locations are in AMG 84 coordinates 4-34

Figure 4-16 Location of interpreted low-permeability geologic structures within the Walloon Coal Measures. Red and green lines indicate interpreted faults. Black lines indicate designated no-flow and no-flow boundaries. Red cells indicate pumping bores. Dark green cells indicate general head boundaries. The central light green area indicates the position of the former Acland underground mine workings. Model dimensions are 13 km x 17 km 4-42

Figure 4-17 Location of interpreted low-permeability geologic structures within the Cecil Plains Sub-Basin. Red crosses indicate the location of approved bores. Roads are indicated in green. Dalby bore = 4996, NAC1 = New Acland 9WB, NAC2 = New Acland 14WB, Prec = New Acland monitoring bore. 44596 = Beef City 1, 87092 = Beef City 2. Model dimensions are 117 km x 102 km. 4-44

Figure 4-18 Predicted off-site groundwater levels at selected sites (existing and simulated bores) during pit de-watering (2006-2028) 4-46

Figure 4-19 Predicted groundwater contours (m AHD) at mine completion during pit de-watering (2006-2028) 4-46

Figure 5-1 Faun Trap Sites and Location of Rare Plants 5-3

Figure 5-2 New Acland Regional Communities 5-4

Figure 5-3 Example of in stream farm dam within Lagoon Creek 5-16

Figure 5-4 Typical stream channel within Lagoon Creek indicating ephemeral status 5-17

Figure 6-1 Seasonal wind roses for Oakey 6-3

Figure 6-2 Wind roses by time of day for Oakey 6-4

Figure 6-3 Dust monitoring locations around New Acland Mine (expanded lease boundary shown) 6-5

Figure 6-4 Frequency of Pasquill stability classes, Oakey, EPA data 6-12

Figure 6-5 Predicted maximum 24-hour PM_{10} concentration (µg/m³), excluding background, for current operations 6-14

Figure 6-6 Predicted annual PM_{10} concentration (µg/m³), excluding background, for current operations 6-14

Figure 6-7 Predicted annual TSP concentration (µg/m³), excluding background, for current operations 6-15

Figure 6-8 Predicted annual dust deposition rate (mg/m^2/day), excluding background, for current operations 6-15

Figure 6-9 Predicted maximum 24-hour PM_{10} concentration (µg/m³), excluding background, for 2015 operations 6-17

Figure 6-10 Predicted annual PM_{10} concentration (µg/m³), excluding background, for 2015 operations 6-17

Figure 6-11 Predicted annual TSP concentration (µg/m³), excluding background, for 2015 operations 6-18

Figure 6-12 Predicted annual dust deposition rate (mg/m^2/day), excluding background, for 2015 operations 6-18

Figure 7-1 Current mine (centre top) and surrounding area with town of Acland (bottom left) - sensitive receivers included in this assessment are numbered 7-2

Figure 7-2 Monthly $L_{A90,15min}$ noise levels for the night period at a number of locations around the existing mine site (Moore and Associates, 2002-2005). 7-3

Figure 7-3 Occurrence of each stability class at Oakey during winter nights (1800 - 0700 hours). 7-6

Figure 7-4 Occurrence of each stability class at Oakey during winter nights (1800 - 0700 hours). 7-7

Figure 7-5 Noise contours for 2007 operational scenario 7-12

Figure 7-6 Noise contours for 2011 operational scenario 7-13

Figure 7-7 Noise contours for 2015 operational scenario 7-14

Figure 7-8 Vibration level reduction with distance from a blast 7-16

Figure 9-1 Sensitive Visual Receptors 9-3

Figure 11-1 Jondaryan Rail Load Out Facility 11-2

Figure 16-1 Locality Plan 16-5

Figure 16-2 Tenures and Real Property Descriptions 16-7

Figure 16-3 The Environmental Management Overview Strategy Framework 16-12